

CONTENTS

LIST OF TABLES	(xii)
LIST OF FIGURES	(xiii)
1 INTRODUCTION	1
2 OBJECTIVES	1
3 PROCESS DESCRIPTION AND TEST EQUIPMENT	2
3.1 Electrodialysis	2
3.2 Experimental site	4
3.3 EDR pilot plant	5
3.4 Pretreatment of feed water to EDR pilot plant	6
4 TEST WORK PROGRAMME	8
5 FINDINGS AND DISCUSSION	9
5.1 Water qualities and salt rejections	9
5.2 Water recovery	13
5.3 Pretreatment	15
5.3.1 Removal of suspended solids	15
5.3.2 Pretreatment for iron and manganese	16
5.3.3 Treatment for preventing barium sulphate scale formation	19
5.4 Operational difficulties	19
5.5 Pilot plant operating costs	20
5.6 Product water uses	21
6 CONCEPTUAL DESIGN AND COST ESTIMATES FOR A COMMERCIAL SCALE PLANT	24
6.1 Conceptual ground arrangement of a 46 l/s (4 000 m ³ /d) EDR plant - 85 per cent recovery	24
6.2 Cost estimation for commercial scale plant	26
6.2.1 Operating cost estimation	26
6.2.2 Capital cost estimation	27
6.3 Brine disposal	28
6.4 Cost summary	28

CONTENTS (continued)

7	CONCLUSIONS	30
8	REFERENCES	33
APPENDIX I	CONVENTIONAL PRETREATMENT REQUIREMENTS FOR EDR ...	34
APPENDIX II	METHODS FOR THE CHEMICAL OXIDATION OF IRON AND MANGANESE	36
APPENDIX III	BARIUM SULPHATE SATURATION LEVELS	38
APPENDIX IV	BACTERIAL COUNTS OF FEED AND PRODUCT WATER	41
APPENDIX V	SUMMARY OF MAJOR EVENTS AND PROCESS DIFFICULTIES DURING THE TEST PERIOD	42
APPENDIX VI	DETAILS OF CONCEPTUAL GROUND ARRANGEMENT FOR A 46 l/s EDR INSTALLATION	47
APPENDIX VII	DETAILS OF OPERATING COST ESTIMATE (JUNE 1990) FOR A 46 l/s EDR INSTALLATION	50

LIST OF TABLES

1.	Mean chemical analyses of EDR process streams - feed, product and brine	9
2.	Pilot plant operating costs incurred, excluding membrane replacement and labour costs	20
3.	Comparison of product water quality with limits for human consumption, hydro-power and effluent discharge ...	22
4.	Bacterial counts on EDR feed and product waters	23
5.	Summary of major components of a 46 l/s EDR installation.	26
6.	Estimated operating cost for a 46 l/s commercial scale EDR plant	27
7.	Cost summary for a 46 l/s EDR installation	29
8.	Total plant cost amortized over 20 years assuring a constant interest rate on capital of 15 per cent and total product flow rate of 53,2 l/s	30
III.1	Degree of saturation of barium sulphate in EDR system ...	40
IV.1	Bacterial counts on EDR feed and product waters	41
VII.1	Estimated operating costs (June 1990) for a 46 l/s (4 M l/d) commercial scale EDR plant	50
VII.2	Electricity consumption at various feed concentrations ..	51
VII.3	EDR membrane stacks - expected life and replacement cost (June 1990)	54

LIST OF FIGURES

1(a)	Movement of ions in a direct current electric field	2
1(b)	A simplified electro dialysis process	3
2.	Simplified flow diagram of the 1,6 l/s EDR pilot plant ...	5
3.	Comparison of dissolved components in feed, product and brine	10
4.	Variation in calcium concentration in feed water	12
5.	Variation of feed and product conductivity and salt rejection based on conductivity	12
6.	Variation of actual product water recovery	14
7.	Variation in turbidity of EDR feed water	17
8.	Iron concentration in raw and pretreated mine water feed .	17
9.	Conceptual ground arrangement for a 46 l/s commercial scale EDR plant	25
III.1	Solubility product for barium sulphate versus ionic strength	38
V.1	Variation of product conductivity, stack amperage and product recovery for the whole experimental period	43